

# STANDARD SPECIFICATIONS and STANDARD DETAILS

## MARCH 2022



CITY OF  
**Tulsa**  
*A New Kind of Energy™*

**CITY OF TULSA  
PUBLIC WORKS DEPARTMENT  
PAUL D. ZACHARY, P.E., CFM DEPUTY DIRECTOR  
175 E. 2<sup>ND</sup> ST., 13 FL.  
TULSA, OKLAHOMA 74103  
(918) 596-9565**

Revised 12.2024

**TABLE OF CONTENTS**  
**SPECIFICATIONS SECTIONS**

**DIVISION I – GENERAL SPECIFICATIONS**

<b><u>PART</u></b>		<b><u>PAGE NO.</u></b>
101	Scope and Location .....	1
102	Scope, Nature, and Intent of Specifications and Drawings .....	1
103	Lines and Grades .....	2
104	Saturday, Sunday, Holiday, and Night Work.....	2
105	Protection of Property .....	2
106	Connections.....	4
107	References to Other Specifications .....	4
108	Protection of Materials .....	5
109	Testing .....	5
110	“Or Approved Equal” Clause.....	6
111	Dewatering.....	6
112	Safety.....	6
113	Removal of Condemned Materials and Structures .....	7
114	Removal and Salvage of Castings.....	8
115	Clean-Up.....	8
116	Placing Work in Service .....	8
117	Submittals .....	9

**DIVISION II – MATERIAL SPECIFICATIONS**

<b><u>PART</u></b>		<b><u>PAGE NO.</u></b>
	Approved Fittings Manufacturers .....	1
201	Concrete .....	4
202	Quick-Setting Flowable Fill .....	13
203	Ductile Iron Pipe, Ductile and Cast Iron Fittings, and Valves .....	15
204	Steel Pipe and Fittings .....	26
205	Reinforced Concrete Pipe and Fittings .....	30
206	Vitrified Clay Pipe and Fittings .....	33
207	Polyvinyl Chloride (PVC) Pipe, Water Service .....	34
207A	High Density Polyethylene (HDPE) Pipe, Water Service .....	34
208	Polyvinyl Chloride (PVC) Pipe, Sewer Service .....	38
209	Castings.....	39
210	Conduit .....	40
211	Vaults, Pits, and Manholes .....	41
212	Sand for Cushion or Backfill.....	42
213	Crushed Stone for Surfacing, Base Course, And Stabilization ...	43
214	RipRap.....	44
215	Corrugated Polypropylene Pipe and Fittings for Stormwater .....	45
216	PVC Drainage Structures.....	47
217	Corrosion Protection of Concrete Wastewater Structures.....	49

**TABLE OF CONTENTS**  
**SPECIFICATIONS SECTIONS**

**DIVISION III – CONSTRUCTION SPECIFICATIONS**

<b><u>PART</u></b>		<b><u>PAGE NO.</u></b>
301	Right-Of-Way Clearing and Restoring.....	1
302	Excavation and Backfill, Unclassified.....	2
303	Mobilization/Demobilization .....	4
304	Contractor Construction Staking .....	5
305	Pipe, Vitrified Clay .....	6
306	Pipe, Reinforced Concrete.....	7
307	Pipe, Ductile Iron .....	8
308	Pipe, Steel .....	9
309	Polyvinyl Chloride (PVC) Pipe, Water Service .....	10
309A	High Density Polyethylene (HDPE) Pipe, Water Service.....	11
310	Locator Wire and Detectable Marking Tape.....	13
311	Tapping of PVC Pipe for Service Connections .....	14
312	Fittings .....	15
313	Polyvinyl Chloride (PVC) Pipe, Sewer Service .....	16
314	Manhole.....	18
315	Connection.....	20
316	Lamphole.....	22
317	Valve.....	23
318	Valve Box.....	24
319	Encasement, Concrete .....	25
320	Cradle, Concrete.....	26
321	Piers, Reinforced Concrete.....	27
322	Conduit, Bored.....	28
323	Structure, Special .....	29
324	Materials Furnished by Contractor and Installed by City.....	30
325	Sodding and Seeding.....	31
326	Street Wash Down.....	32
327	Traffic Control Devices.....	33
328	Bore .....	34
329	Pavement Removal and Replacement .....	35
330	Erosion Control Measures .....	37
331	Water Table Cradle.....	38
332	Conduit, Open Cut.....	39
333	Removal, Salvage, Abandonment of Existing Facilities .....	40
334	Construction As-Builts.....	43
335	Acceptance Sampling/Testing Requirements .....	45
336	Pavement and Bridge Deck Smoothness Revised 04.25.24.....	55

**TABLE OF CONTENTS**  
**SPECIFICATIONS SECTIONS**

**DIVISION IV – SANITARY SEWER REHAB CONSTRUCTION SPECIFICATIONS**

<b><u>PART</u></b>		<b><u>PAGE NO.</u></b>
400	General Provision .....	1
401	Site Preparation .....	8
402	Restoration .....	11
403	Backfill .....	19
404	Removal, Salvage, and Abandonment of Existing Facilities .....	22
405	Pipeline and Installation .....	23
406	Pipe Reaming .....	27
407	Pipe Crushing .....	32
408	Pipe Bursting .....	38
409	Sliplining .....	44
410	Cured-in-Place Pipe.....	55
411	Pipeline Pressure Grouting.....	67
412	Point Repairs .....	73
413	Concrete Embankment .....	76
414	Clay Dam.....	79
415	Construction Television Inspection of Sanitary Sewer .....	80
416	Complete Manhole Replacement.....	83
417	Replacement of Cleanout / Lamphole and/or Cleanout / Lamphole Frame and Cover .....	86
418	Replacement of Manhole Frame and Cover, Frame Seal, Chimney, and Grade Adjustment .....	90
419	Patching, Repairs, and Plugging Lift Holes.....	98
420	Manhole Step Removal and Replacement.....	100
421	Interior Manhole Rehabilitation – Corbel (Cone) and Wall Rehabilitation, Bench and Invert, and Pipe Seal Rehabilitation .....	102
422	Manhole Testing of New and Rehabilitated Manholes.....	112
423	Obstruction Removal .....	115
424	Cured-in-Place Sectional and Spot Repair .....	117
425	Sealed Manhole Frame and Cover .....	122

**TABLE OF CONTENTS**  
**SPECIFICATIONS SECTIONS**

**DIVISION V – WATER METER SPECIFICATIONS**

<b><u>PART</u></b>		<b><u>PAGE NO.</u></b>
	Approved Meter and Back Flow Preventer Manufacturers.....	1
500	Definitions .....	2
501	Displacement Water Meters – 5/8” x 3/4”, 1”, & 1-1/2” .....	4
502	Compound Type Water Meters – 2”, 3”, 4”, 6”, & 8” .....	7
503	Turbine Water Meters – Irrigation and Special Services – 2” & 3” ...	11
504	Turbine Meters – Fire Service – 4”, 6”, 8”, & 10” .....	14
505	Fire Flow Meters – 4”, 6”, 8”, & 10” .....	17
506	Double Check Detector Assembly – 4”, 6”, 8”, & 10” .....	20

**DIVISION VI – TRAFFIC SPECIFICATIONS – MATERIALS**

<b><u>PART</u></b>		<b><u>PAGE NO.</u></b>
601	Pull Boxes.....	1
602	Electrical Conduit.....	4
603	Signal Pole Footings.....	12
604	Loop Detectors .....	15
605	NOT USED	
606	Pre-Emption and Signal Priority Systems .....	21
607	Power Supplies.....	23
608	Traffic Signs.....	27
609	NOT USED	
610	Traffic Signal Controller Cabinet Assembly.....	29
611	Electrical Conductors Traffic Signal .....	40
612	Cabinet Bases, Aprons, and Guards .....	44
613	Pedestrian Push Button .....	46
614	LED Traffic Signal Heads and Pedestrian Signal Heads .....	48
615	Base Covers .....	54
616	Mast Arm Brackets .....	55
617	Signal Poles and Mast Arms.....	56
618	Bonding.....	60
619	Temporary Signals.....	62
620	Video Detection System.....	64
621	Highway, Street, and Pedestrian Lighting .....	66
622	Wireless Traffic Signal Communications System.....	78
623	Battery Backup .....	80
624	Remove and Reset Existing Traffic Signal Controller Assembly.....	83
625	Removal of Traffic Items .....	84
626	Traffic Signal Construction and Operation .....	86
627	Pre-Qualification for Traffic Operations Materials .....	93
628	Signal and Lighting Project Contractor Experience Requirements ...	98
629	Signs Assemblies with Flashing Beacons.....	100
630	Rectangular Rapid Flashing Beacons.....	106

**TABLE OF CONTENTS**  
**SPECIFICATIONS SECTIONS**

**DIVISION VII – WATER & SEWERE STANDARDS**

<b><u>PART</u></b>		<b><u>PAGE NO.</u></b>
701	Special Requirements, New Equipment Purchases.....	1
702	Preferred Manufacturers, New Equipment Purchases.....	1

**DIVISION VIII – STREETScape SPECIFICATIONS**

<b><u>PART</u></b>		<b><u>PAGE NO.</u></b>
800	Decorative Lighting .....	1
810	Brick Unit Pavers.....	19
811	Interlocking Concrete Pavers.....	32
812	Stamped Concrete Finishing.....	43
820	Streetscape Amenities .....	55
830	Structural Soil .....	65
831	Trees, Shrubs, and Ground Cover.....	72
832	Sodding.....	78
833	Landscaping Maintenance .....	84
840	Underground Sprinkler System.....	89

**STANDARD DETAILS INDEX**  
(found in small book)

**STANDARD DETAILS INDEX**  
(found in small book)

101	Fire Proof Area
102	Project Sign
103	Guidelines for Blasting Sign
301	NOT USED
302	Conduit for Future Service Lines
303	NOT USED
304	Bedding Detail – Rigid Pipe
304A	Trench Detail – Waterline
305	Bedding Detail – Flexible Pipe
306	NOT USED
307	Bore/Open Cut Conduit Detail
308	Combination Air Vacuum / Air Relief, Check Valves, and Vaults
309	Fire Hydrant
310	Blowoff Hydrant
311	Sampling Tap on 4” – 12” Water Lines
312	Frame and Lid for Water Vaults
313	Valve Box
313A	Valve Box
314	Manhole Steps
315	Thrust Blocks and Trench Conditions
316	HDPE Tee Details
317	HDPE – Ductile Iron Fitting Details 1 of 2
319	HDPE Splice and Fire Hydrant Detail
320	HDPE Realignment Details
321	HDPE Wall Anchor Details
351	Bedding Detail PVC Flexible Sanitary Sewer Pipe
352	Frame and Lid for Manholes
353	Frame and Lid for 4’ I.D. Sanitary Manhole
354	Frame and Lid for 5’ I.D. and Larger Sanitary Manhole
355	Brick Manhole (Special Approval Only)
356	Sanitary Sewer Manhole with Taper
357	Sanitary Sewer Manhole with Flat Slab Top
358	Pre-Cast Sanitary Sewer Manholes
359	NOT USED
360	Frame and Lid for Lampholes
361	In-Line Tees for Service Connection
362	Riser Detail
363	Riser Detail with Sloped Trench
364	Sanitary Sewer Combination Air Relief Valve Installation
365	Go, No-Go Deflection Testing Mandrel
366	Manhole Step Location and Invert Details
367	Water Table Cradle

**STANDARD DETAILS INDEX**  
**(found in small book)**

- 401 Manhole Grade Adjustment
- 401A Concrete Collar for Partial Manhole Replacement
- 402 Cover, Frame, and Frame Seal Repair
- 403 Special Detail for Interior Coating System
- 404 Step Removal
- 405 Rubber Seal at Manhole
- 406 Shallow Flattop Manhole
- 407 Bench and Invert Rehabilitation
- 408 Excavation and Restoration at Grade and Above Grade Construction
- 409 Concrete Manhole Collar
- 410 Corbel (Cone) Replacement
- 411 Chemical Pressure Grouting – Precast Manhole
- 412 Chemical Pressure Grouting – Brick Manhole
- 413 Patch Hole and Plug Lift Hole
- 414 Manhole Adjusting Ring
- 415 Clay Dam
  
- 501 Standard Meter Settings for 5/8" x 3/4" and 3/4" Water Service
- 501A Standard Meter Settings for 5/8" x 3/4" and 3/4" Water Service (AquaPEX Blue)
- 502 Standard Meter Settings for 1" Water Service
- 502A Standard Meter Settings for 1" Water Service (AquaPEX Blue)
- 503 Standard Meter Settings for 1-1/2" Water Service
- 504 Standard Meter Settings for 2" Water Service
- 505 Meter Can with Rim and Lid 3/4", 1", and 1-1/2" Water Meter Can Installation
- 506 Meter Can with Rim and Lid 1-1/2" Water Meter Installation
- 507 Meter Can with Rim and Lid 2" Water Meter Installation
- 508 Offset Plug
- 509 Typical Utility Crossing of Raw Water Flowlines (RWF)
  
- 607B Traffic Signal SVC Pole
  
- 701 Residential Concrete Driveway Concrete Street
- 702 Residential Concrete Driveway Asphalt Street
- 703 Residential Asphalt Driveway Concrete Street
- 704 Residential Asphalt Driveway Asphalt Street
- 705 Residential Drive No Curb
- 706 Commercial Driveway
- 707 Commercial Driveway
- 708 Commercial Asphalt Driveway
- 709 Parking Lots
- 710 Temporary Commercial Driveway (No Curb)
- 711A Access Management
- 711B Residential Driveway Access Management
- 712 Radius Protector
- 713 Pavement Removal and Replacement
- 714 Pavement Cuts
- 715 HWY-PVT-RPL for State Highways that are Arterial Streets



**STANDARD DETAILS INDEX**  
**(found in small book)**

751	Pipe Bedding Detail for Storm Sewer
752	Frame and Lid for Stormwater Manholes
753	Frame and Lid for 4' and 5' I.D. Stormwater Manhole
754	Frame and Lid for 6' and 8' I.D. Stormwater Manhole and Junction Boxes
755	Configurations of Cast Iron Curb Inlets
756	Private Storm Sewer Connected to Public Storm Sewer
757	Public or Private Storm Sewer Connected to Public Storm Sewer
758	Residential Storm Water Curb Opening
793	Residential Drive Asphalt or Concrete No Curb
800	Street Light Standard Acorn Pole and Fixture
801	Blue Dome Pole and Fixture
802	Street Light Standard Type Ball Field
803	Street Light Standard Lighting Controller and Schematic
804	Pole Base Details for Standards 800, 801, 802
805	Shallow Light Pole Base Detail
806	Street Light Standard – River Parks Pole and Fixture
810	Brick Paver Sidewalk
811	Concrete Paver Sidewalk
812	Permeable Pavement with Full Exfiltration to Soil Subgrade
813	CBD Curb Cut
814	Bike Corral Detail
815	Parking Lot Screen Trellis
820	Bench
821	Bollard – Cast
822	Bollard – Surface Mounted
823	Bollard – Removable
824	Bike Rack
825	Trash Receptable
830	Tree Well Without Tree Grate
831	Structural Soil
832	Tree Grate Frame and Concrete Base
833	ADA Tree Grate Set
834	Tree Well with Grate

**STANDARD DETAILS INDEX**  
**(found in small book)**

840	Irrigation Enclosure
841	Backflow Preventer Installation
842	Automatic Controller Installation
843	Remote Control Valve Installation
844	Drip Line with Check Valve Two Ring Detail
845	Drip Line with Check Valve Three Ring Detail
846	Drip Line with Check Valve Multiple Shrub Ring Detail
847	Drip Line with Check Valve Slope Layout, 1 Valve
848	Drip Line with Check Valve Center Feed Layout
849	Manual Tree Irrigation
850	Manual Tree Irrigation (Vertical)

**STANDARD DRAWINGS INDEX**  
**(found in large book)**

126	Standard Silt Fence and Construction Entrance
325	Ball Valve Vault Standard For 16" & 24" Lines Under H-20 Loading
326	Ball Valve Vault Standard For 30" thru 48" Line Under H-20 Loading
327	Combination Air Vacuum/Relief Valve Vault for 2" ARV Less Than 5 lbs. in Weight
328	Standard 4", 6", and 8" Air Valve Assembly On 16" thru 48" Main
329	Standard 8" and 12" Blowoff Assembly
330	Cathodic Protection
331	Details for 6' – 8' Sanitary Sewer Manholes
525	3" Meter Standard and Vault Assembly
526	3" Meter with Pressure Sustaining Valve Assembly and Vault
527	4" Meter Assembly and Vault
528	4" Meter with Pressure Sustaining Valve Assembly and Vault
529	6" Meter Standard and Vault Assembly
530	6" Meter with Pressure Sustaining Valve Assembly and Vault
531	8" Meter Standard and Vault Assembly
532	8" Meter with Pressure Sustaining Valve Assembly and Vault
533	10" Meter Standard and Vault Assembly
534	10" Meter with Pressure Sustaining Valve Assembly and Vault
550	Backflow Prevention Options Index
551	4", 6", 8" Detector Check Assembly and Meter Can
552	4" – 10" Detector Check Assembly and Vault
553	4" – 10" Double Check Detector and Vault Assembly
601	Pull Box Installation
602	Conduit Installation
603	Signal Pole Footing Details
604A	Installation of Detectors
604B	Detector Wire Installation
605	NOT USED
606	Emergency Pre-Emption Detail
607A	Traffic Signal Service Pole and Service to Signal Standard
607B	Traffic Signal Pedestal Service
608A	Street Name Signs
608B	Traffic Signs
609	NOT USED
610A	332 Controller Cabinet Detail
610B	336S Controller Cabinet Detail
610C	332 Cabinet Wiring
611A	Pole Wiring Detail
611B	Downtown Pedestal Wiring Detail
611C	Pole Wiring Detail
612	Cabinet Guard Detail
613	Pedestal and Mast Arm Pole Details

**STANDARD DRAWINGS INDEX**  
**(found in large book)**

614A	Traffic Signals and Accessories
614B	Signal Head Wiring
615	NOT USED
616	Mast Arm Brackets
617A	Signal Poles and Mast Arms
617B	Single Mast Arm Details
618	Bonding Diagram
619	NOT USED
620	NOT USED
621A	Lighting Controller Details
621B	Lighting Wiring Details
629A	Solar Powered School Flasher Detail
629B	Electric Powered School Flasher Detail
725	Standard Pavement Patch and Repair
726	Asphalt Pavement Standard Details for Alleys, Residential, and Collector Streets
727	Concrete Pavement Standard Details for Alleys, Residential, and Collector Streets (1 of 2)
728	22' Asphalt Speed Hump
729	Concrete Pavement Standard Details for Alleys, Residential, and Collector Streets (2 of 2)
730	Standard Asphalt Pavement Cut and Repair
731	Standard Concrete Pavement Cut and Repair
732	All-Weather Parking Surfaces for Light Duty Residential Parking
733	Standard Pavement Rehabilitation for Utility Construction
761	Standard Inlets and Grates w/Access Manhole Back of Curb
762	Precast Standard Inlets and Grates w/Access Manhole Back of Curb
763	Standard Masonry Stormwater Inlets (for rehab and reference only)
764	Standard Reinforced Concrete Stormwater Inlets
765	Standard Stormwater Frames
766	Standard Stormwater Grates
767	Standard Cast Iron Curb
768	Standard Recessed Curb Inlet
769A	Recessed Curb Inlet RCI 0648 – 6" Throat, RCI 1048 – 10" Throat
769B	Recessed Curb Inlet RCI 0696 – 6" Throat, RCI 1096 – 10" Throat
770	Standard Drop Inlet 15", 18", and 24"
771	Standard Drop Inlet 30", 36", and 42" with no Access Manhole
772	Standard Drop Inlet 48" Pipe
773	Standard Three Way Drop Inlet 48" Pipe
774	Standard Masonry Manhole and Junction Box (for rehab and reference only)
775	Standard Precast Concrete Stormwater Manhole
776	Standard Pipe Headwalls 15" to 42"
777	NOT USED
778	Grouted RipRap Protection for Existing Headwall (for reference only)
779	Standard Energy Dissipator

**STANDARD DRAWINGS INDEX**  
**(found in large book)**

780	Standard Baffle Block Energy Dissipator
781A-D	Semi-Elliptical Storm Sewer (for rehab and reference only)
782	Standard Low-Flow Concrete Channel Typical Layout (for rehab and reference only)
783	Concrete Lined Channel (for rehab and reference only)
784	Vertical Wall Channel (for rehab and reference only)
785	Standard Dikes and Swales
786	NOT USED
787	Sidewalk Grate for Tree Well
788	Single Pole Gate
789	Double Pole Gate
790	Standard Sidewalk Ramp
791	Special Type I Drop Inlet
792	Special Type II Drop Inlet

